



LOCATION MAP
SCALE: 1"=2000'

Found / Set Monuments
(Unless Otherwise Noted)

- FND #4 BAR
- SET #3 BAR w/ "J&A 1484" CAP
- FND MAG NAIL IN "J&A 1484" SHINER
- FND #4 BAR w/ "CA 3949" CAP

Survey Legend

BENCHMARK	ROOF DRAIN
CONTROL POINT	BORE HOLE
FOUND MONUMENT	ROUND POST
SET MONUMENT	SQUARE POST
FIRE HYDRANT	EVERGREEN TREE
AUTOSPRINKLER	DECIDUOUS TREE
HOSE BIB/SPIGOT	BUSH
WATER METER	GATE
WATER VALVE	HANDICAP
WATER WELL	TRAFFIC SIGNAL POLE
SPRINKLER HEAD	STOCKADE FENCE
SPRINKLER VALVE	CHAINLINK FENCE
SANITARY MANHOLE	BARBED WIRE FENCE
CLEANOUT	WATERLINE
STORM MANHOLE	STORM SEWER
STORM GRATE	SANITARY SEWER
CURB INLET	GAS LINE
FIELD INLET	UNDERGROUND TELEPHONE
GAS METER	UNDERGROUND POWER
NO GAS METER	UNDERGROUND CABLE
GAS VALVE	OVERHEAD CABLE
VENT PIPE	RAILROAD TRACKS
MONITORING WELL	EXISTING CONTOUR
POWER POLE	BRUSH LINE
GUY WIRE	ASPHALT PAVING
LIGHT POLE	CONCRETE PAVING
GROUND LIGHT	FLOWLINE
ELECTRIC BOX	TOP OF GRATE
ELECTRIC METER	TOP OF RIM
ELECTRIC MANHOLE	FINISH FLOOR
ELECTRIC BREAKER	CORRUGATED METAL PIPE
ELECTRIC OUTLET	REINFORCED CONC. PIPE
PULL BOX	REINFORCED CONC. BOX
TELEPHONE BOX	TOP OF CURB
TELEPHONE MANHOLE	CURB GUTTER
CABLE BOX	BUILDING LINE
MANHOLE	UTILITY EASEMENT
UTILITY BOX	RIGHT-OF-WAY
MAILBOX	RECORD
SIGN	MEASURED
AIR CONDITIONER	CORRESPONDING NOTE

******** NOTE ********

THIS SURVEY MEETS OR EXCEEDS THE REQUIREMENTS SET FORTH BY THE "OKLAHOMA MINIMUM STANDARDS FOR THE PRACTICE OF LAND SURVEYING" AS ADOPTED BY THE OKLAHOMA STATE BOARD OF REGISTRATION FOR PROFESSIONAL ENGINEERS AND LAND SURVEYORS.

The surveyor has utilized information from a Utility Atlas obtained from the City of Oklahoma City combined with observed evidence of utilities on the ground to create an overall view of the underground utilities affecting the subject tract. However, lacking excavation, the exact location of underground features cannot be accurately, completely, and reliably depicted on the survey. The surveyor makes no guarantees that the underground utilities shown hereon comprise all such utilities in the area, either in service or abandoned. The following is a list of companies provided as a result of a Company List Request submitted to the Oklahoma One-Call System (Call Okie): The reference number for this request is 230316102281469.

- OG&E OKC/HCA
- USIC/Cox Comm/OKC
- USIC/Dobson/OneNet
- USIC/OG&E OKC METRO
- Oklahoma Natural Gas - West
- OKC/Public Works
- OKC/Water&Waste
- IndianNation/CheckTel
- OK State of/ODOT
- AT&T Distribution

According to the atlas provided by the City of Oklahoma City, there is currently no active waterlines or sanitary sewer lines on the subject tract

Certificate of Survey

I, Matthew Johnson, a Professional Land Surveyor in the State of Oklahoma, do hereby certify to:

- Oklahoma City Urban Renewal Authority, a public body corporate
- American Eagle Title Insurance Company
- First American Title Insurance Company

This is to certify that this map or plat and the survey on which it is based were made in accordance with the 2021 Minimum Standard Detail Requirements for ALTA/NSPS Land Title Surveys, jointly established and adopted by ALTA and NSPS, and includes Items 1, 2, 3, 4, 7(a), 8, 9, 10, 11(a), 16 and 18 of Table A thereof. The field work was completed on March 13, 2023.

Date of Plat or Map: March 21, 2023

Matthew Johnson, P.L.S.
Registration No. 1807
JOHNSON & ASSOCIATES
Certificate of Authorization No. 1484

LICENSED PROFESSIONAL LAND SURVEYOR
MATTHEW JOHNSON
1807
OKLAHOMA

Surveyor's Note:

Address: None provided
Parcel ID: R020145795

No portion of the property shown on the survey lies within a Special Hazard Area, as described on the Flood Insurance Rate map for the community in which the subject property is located. The entire parcel lies within Zone "X" of the Federal Emergency Management Agency Community Panel Number 40109C0285H Map with an effective date of December 18, 2009.

The subject tract is currently zoned DBD (Downtown Business District) with DSHA overlay (Downtown Scenic Highway Area).
Source: the City of Oklahoma City, Oklahoma Planning Department website at www.okc.gov. Phone 405-297-2623 for more information about Building Height, setback and parking restrictions for this zoning.

There are no striped parking spaces on this tract.

There was no evidence of recent earth moving work, building construction or building additions observed in the process of conducting the field work.

The subject tract is contiguous with the adjoining properties along their common boundaries with no gaps or overlaps.

As depicted on the survey, the subject tract has access to North Walnut Avenue (a public street).
Note: Pursuant to Exception No. 10, the accessible width is limited to 35 feet.

Basis of Bearing: Grid North as established by state plane datum (Oklahoma State Plane North Zone NAD83).
All distances are Grid distances in U.S. Survey feet.

Legal Description:

A strip, piece, or parcel of land lying in part of Blocks 29 and 36, Maywood Addition to the City of Oklahoma City, and all that part of N.E. 6th Street, lying between Blocks 29 and 36 and lying in part of the alley in Block 36, all lying in the northwest quarter of Section 34, Township 12 North, Range 3 West in Oklahoma County, Oklahoma. Said parcel of land being described by metes and bounds as follows:
COMMENCING at the southwest corner of Lot 17 of said Block 36;
THENCE North 00°07'16" West along the west line of said Lot 17, a distance of 55.49 feet;
THENCE North 89°52'44" East a distance of 10.00 feet to the POINT OF BEGINNING;
THENCE North 00°07'16" West and parallel with the west line of said Lot 17, a distance of 121.21 feet;
THENCE northeasterly on a curve to the left having a radius of 149.46 feet and a chord bearing of North 26°24'11" East and a chord distance of 172.62 feet, an arc distance of 184.03 feet;
THENCE North 50°58'57" East a distance of 107.10 feet;
THENCE South 39°01'03" East a distance of 271.76 feet;
THENCE South 50°58'57" West a distance of 88.34 feet;
THENCE southwesterly on a curve to the right having a radius of 530.20 feet and a chord bearing of South 65°27'34" West and a chord distance of 265.09 feet, an arc distance of 267.93 feet;
THENCE North 32°01'53" West a distance of 39.65 feet to said POINT OF BEGINNING.

Note: The above legal description lies wholly within the three following described tracts of land, when taken together:

1. Lots 3 through 16, both inclusive, Block 36, Maywood Addition to Oklahoma City, Oklahoma County, Oklahoma according to the plat recorded in Book 1 of Plats, page 20 and the south half of 6th Street adjoining said Lots 3 through 16, both inclusive, and the north half of the 20 foot east-west alley in said Block 36 which adjoins said Lots 3 through 16, both inclusive;
2. Lots 17 through 28, both inclusive, Block 36, Maywood Addition to Oklahoma City, Oklahoma according to the plat recorded in Book 1 of Plats, page 20 and the south half of the 20 foot east-west alley in said Block 36 which adjoins said Lots 17 through 28, both inclusive
3. All that part of Block 29, in Maywood Addition to Oklahoma City, Oklahoma County, Oklahoma, according to the plat recorded in Book 1 of Plats, page 20, described as follows, to-wit:
COMMENCING at the southwest corner of said Block 29;
THENCE east on the property line of said Block 29, 125 feet;
THENCE in a northwesterly direction 84.25 feet, more or less, to a point on the property line, which said point is 125 feet from the southwest corner of said Block;
THENCE in a southwesterly direction on the property line of said Block, 125 feet to the point or place of beginning, and the north half of 6th Street which adjoins said part of Block 29

The following items refer to Schedule B - Part II of the First American Title Insurance Company Title Commitment No. 2301-0009-23, dated January 21, 2023 at 7:30 A.M.:

Exception No.	Recording Information	Description of Easement	Applicable	Plotted	Note
9	Book PL1, page 20	Dedication to the public of Sixth Street and the east-west alley on the plat of Maywood Addition	Yes	Yes	
10	Book 15031, page 1144	Conditions, restrictions and reservation of rights of access set forth in Quit Claim Deed	Yes	Yes	A
11	Book 15031, page 1144	Any utility easements, licenses or permits which do not appear in the public records as discussed in Quit Claim Deed	Yes	No	
12		Assessments which become due and payable subsequent to the Date of Policy as a result of the Land being located in an Oklahoma City Business Improvement Assessment District	Yes	No	
13		Conditions pertaining to the manufacture, sale or disposal of intoxicating liquor or beer set forth in the following, which provide for forfeiture of title upon violation thereof			
13a	Book 2, page 37	Warranty Deed	Yes	No	
13b	Book 1, page 450	Warranty Deed	Yes	No	
13c	Book 1, page 420	Warranty Deed	Yes	No	
13d	Book 1, page 448	Warranty Deed	Yes	No	
13e	Book 1, page 451	Warranty Deed	Yes	No	
13f	Book 1, page 548	Warranty Deed	Yes	No	

Note	Surveyor's Comment
A	The existing Limits of Access are depicted on the survey, pursuant to the following text as recorded in the deed: "Grantor, reserves and excepts unto itself, its successors and assigns ALL PREVIOUSLY ACQUIRED RIGHTS OF ACCESS from said 1.5940 acres, more or less to the lands or right-of-ways covered by the abutting the Interstate Highway No. 235 Limited Access Highway, Harrison Street and NE 6th Street facilities, except, that the Lessee shall be allowed one (1) point of ingress and egress within the North 35.00 feet of Lot 17, Block 36."

Copyright © 2023 Johnson & Associates

NO.	REVISIONS DESCRIPTION	DATE

Johnson & Associates
1 E. Sheridan Ave., Suite 200
Oklahoma City, OK 73104
405.235.8075 Fax 405.235.8078
survey@jaokc.com www.jaokc.com
Certificate of Authorization #1484 Exp. Date 06-30-2023
• ENGINEERS • SURVEYORS • PLANNERS •

NE 5th & WALNUT
ODOT PARCEL 16 FLATIRON
OKLAHOMA CITY, OKLAHOMA COUNTY, OKLAHOMA
ALTA/NSPS LAND TITLE SURVEY

Proj. No.:	4597.001
Date:	3-21-2023
Scale:	1"=40'
Surveyed By:	CT
Drawn By:	MJ/NB
Approved By:	MJ

SHEET NUMBER
1of1

SOURCE DOCUMENTS: 4597001-Legal.dwg, 4597001-Survey.dwg, 3371-SIG.dwg
PATH: I:\2021\4597.001\Survey\4597001-Survey.dwg 3371-SIG.dwg