

THE CITY OF OKLAHOMA CITY

APPROVAL SHEET

Project No. TC-0598
Intersection Improvements
NW Expressway and Lake Hefner Parkway

Prepared by:


CEC Corporation
4555 W. Memorial Road
Oklahoma City, OK 73142
405-753-4200



Kyle Morse, P.E.




Recommended for Approval



Deborah K. Miller, P.E., Interim Director
Public Works/Interim City Engineer


APPROVED by the City of Oklahoma City this 16TH day of JANUARY,
2024

ATTEST:



City Clerk





Mayor

PRELIMINARY DESIGN REPORT

FOR

CITY OF OKLAHOMA CITY
OKLAHOMA CITY, OK

INTERSECTION IMPROVEMENTS
TC-0598 – NW EXPRESSWAY AND LAKE HEFNER PARKWAY

12/14/23



CEC Corporation
4555 West Memorial Rd,
Oklahoma City, OK 73142
Phone: 405.753.4200
www.connectcec.com

12/14/23
PRELIMINARY ENGINEERING REPORT

INTERSECTION IMPROVEMENTS
TC-0598 – NW EXPRESSWAY AND LAKE HEFNER PARKWAY

TABLE OF CONTENTS

TABLE OF CONTENTS	2
EXECUTIVE SUMMARY	2
DECISION MATRIX	4
INTRODUCTION	5
EXISTING CONDITIONS	6
PROPOSED IMPROVEMENTS	10
OTHER CONCEPTS	12
DRAINAGE	15
PRELIMINARY COST ESTIMATES	16
RECOMMENDATIONS	16

APPENDICES

PRELIMINARY COST ESTIMATE	APPENDIX A
PRELIMINARY CONSTRUCTION PLANS	APPENDIX B
ALTERNATE 1 EXHIBIT AND ESTIMATE	APPENDIX C

EXECUTIVE SUMMARY

Scope

CEC was retained by the City of Oklahoma to provide plans and construction documents for TC-0598 intersection improvements for the intersection of NW Expressway and the north bound off ramp of Lake Hefner Parkway, a street development project. The City of Oklahoma City has been awarded an ACOG grant (Association of Central Oklahoma Government) for construction, which will be administered by ODOT (Oklahoma Department of Transportation), 80% ACOG/ODOT and 20% OKC street development. The overall focus of the project is to add additional capacity and reduce the congestion of the identified intersection within Benefit Area C1. See Figure 1 below.




Figure 1: TC-0598 Project Location

Through its analysis of traffic operations, this traffic study recommended the extension of storage length for the westbound traffic turning right on NW Expressway and for northbound traffic turning right from the exit ramp from Lake Hefner Parkway. It was determined, essentially, that a single turn bay provided enough capacity for projected traffic but that these movements were limited by the fact that the turn bays were short and long lines of traffic frequently prevented vehicles from reaching them. This has also been

observed through experience of CEC staff and during field observation during afternoon rush hour. For this study, CEC has investigated these options, and others, for feasibility.

Summary

This Study analyzes key recommendations of a prior study for feasibility and investigates additional improvements that can be incorporated to improve traffic operations. The following improvements are recommended for this intersection as the Base Bid:


- Northbound Lake Hefner Parkway exit ramp
 - Extend the right turn bay to provide a total of 510 feet of storage.
 - Reconstruct the vertical profile of the right turn bay to flatten out the grade vehicles accelerate out of and raise the elevation to improve sight distance.
 - Make minor adjustments to the northbound through/left stop bar to keep lines of sight clear.
 - Relocate the traffic signal pole that serves eastbound NW Expressway to clear sight obstruction.
- Westbound NW Expressway
 - Extend the right turn bay to provide a total of 800 feet of storage.

A project kick-off meeting was held on September 6, 2023 to discuss the project scope with City of Oklahoma City staff. The City of Oklahoma City has been awarded an ACOG grant, Association of Central Oklahoma Governments, which will be administered by ODOT, Oklahoma Department of Transportation, 80% ACOG/ODOT and 20% OKC construction cost. See figure below.

Budget	ACOG/ODOT	OKC
Preliminary Base Bid /w Alt 1. Cost Estimate	\$1,134,669	\$283,667
Fixed Limit of Construction Budget	\$1,686,563	\$421,641
Total Under Construction Budget	\$551,894	\$137,974

A combination of ODOT and City of Oklahoma City funding will be used for construction. ODOT standards and specifications will be used for the proposed design.

Project Schedule



Estimated Construction Duration: 8 months

DECISION MATRIX

Base Bid: TC-0598	
Advantages	Disadvantages
✓ Improves Intersection Performance	✗ Construction in high traffic roads
✓ Significantly improved right turn performance	
✓ Significantly improved right turn performance	
✓ Improved sight distance and safety	
✓ \$1,444,927 Construction Cost, Under budget	

Add Alternate 1: TC-0598	
Advantages	Disadvantages
✓ Westbound right turn becomes free flowing, a modest increase over existing performance	✗ Construction in high traffic ramp
✓ Removes conflicts with northbound through moving vehicles	✗ Modest improvement relative to cost
✓ Would still be under budget if incorporated	

Recommendation

After considering multiple solutions, CEC recommends the Base Bid and Add Alternate for the intersection of Hefner Parkway with NW Expressway which includes the following:

- Lengthen the existing westbound right turn bay on NW Expressway to provide 800 total feet of storage.
- Reconstruct the northbound right turn bay on the Lake Hefner Parkway exit ramp and lengthen to provide a total of 510 linear feet of storage length.
 - Revised geometrics will improve sight distance and aid acceleration onto NW Expressway. The northbound left stop bar will also be shifted back, and the existing signal pole servicing eastbound traffic will be relocated to improve visibility.
- Upsize four storm sewer inlets.
- Widen the Northbound entrance ramp for a dedicated lane to receive westbound right traffic.

INTRODUCTION

This report summarizes the preliminary design considerations for the City of Oklahoma City Project No. TC-0598 intersection improvements along NW Expressway and Lake Hefner Parkway. The report outlines the existing conditions of the roadway and lengthening of existing right turn bays along with several conceptual layouts. Proposed improvements to lengthen the northbound right and westbound right turn bays are as previously recommended in the traffic study submitted in November 2022 which analyzed traffic operations at this location. The project location is shown in Figure 2.



Figure 2- Project Location (Google Maps)

A project kick-off meeting was held on August 1, 2023, between the City of Oklahoma City and CEC staff. The City of Oklahoma City Public Works department requested improvements for this project along NW Expressway and Lake Hefner Parkway. These improvements are discussed in further detail in the following sections. The total budget allotted for construction of the roadway is \$1,071,310.

EXISTING CONDITIONS

Roadway Facilities

Project extents for TC-0598 is centered at the intersection of NW Expressway with Lake Hefner Parkway's northbound on and off ramps. Lake Hefner Parkway is a six-lane highway with four ramp-terminal connections to NW Expressway, which is also a six-lane facility. Vehicles exit northbound Lake Hefner Parkway on a 40 mph off ramp and approach NW Expressway in three different lanes. These lanes are a protected northbound left, a shared northbound/northbound through lane, and a northbound right turn bay with 325 feet of storage length that is yield controlled. This yield-controlled right enters at an angle to Expressway to accommodate WB-67 trucks. While the angle of entry is unavoidable, there are additional factors that complicate entering Expressway and therefore reduce the through capacity of this movement. See Figure 3 below.



Figure 3- Looking back, leaning over steering wheel.

The above image was taken from the passenger seat of a Ford Explorer. In addition to the acute angle resulting from radii to accommodate semi-truck traffic, this turn lane is also at a 2.6% upgrade as it approaches Expressway which negatively affects vehicle acceleration and sets vehicles 10 inches below the adjacent eastbound lane. This might not be as much of an issue for a Ford Explorer but would present greater difficulty to a compact car with a lower riding height. These additional considerations exacerbate the driver's ability, or level of comfort, to find a suitable gap in cars to turn into and thereby reduces capacity of this movement. These are issues we will alleviate with this project. Additionally, it is worth noting that a silver vehicle had crept past the stop bar and that in combination with the base of the

existing signal pole greatly limited sight distance for yield controlled vehicles right turning vehicles. A zoomed version of the same picture is below.



Figure 4: Sight Obstructions

The traffic control sign was corrected after the picture was taken but the other two sources of obstruction need to be addressed so vehicles can see to the west end of the bridge and more comfortably find gaps in traffic. NW Expressway is signed for 45 mph and its westbound approach to the northbound Hefner Parkway Ramps includes four lanes, three of which are westbound through lanes and the fourth is a westbound right turn bay that currently has 270 feet of storage length.

On the north side of NW Expressway, there is an entrance to a housing addition and 5 commercial drives serving multiple businesses. On the south side of NW Expressway is one of the primary entrances for Integris Baptist Medical Center that is also the main point of access for the emergency room and sees regular traffic from medical ambulances. The hospital helipad is located on the southeast corner of the intersection. The required helipad clear area depends on the size of the helicopter according to the Federal Aviation Administration. Preliminary calculations based on a Huey type helicopter with a 48-foot rotor indicate that the clear area is possibly touching, or slightly overlapping with some of the existing fence. For this reason, we will coordinate TC-0598 construction activities with Integris and will avoid disturbing the existing fence or otherwise creating flight obstructions near this clear area.

Traffic and Accident History

As discussed in the previously submitted TC-0598 traffic study, the NW Expressway corridor sees approximately 40,000 AADT. According to this traffic study, this intersection operates at the Level of Service (LOS) C and is projected to decline to LOS F by 2042. Key challenges in present day traffic operations for this intersection are regarding low performance of the westbound right turn bay on Expressway and the right turn bay for the northbound off ramp on Hefner Parkway. In both instances it was determined that the limiting factor was not the volume of turning traffic or how traffic was controlled. Instead, performance was limited by the queue lengths from primary movements blocking cars from entering the short right turn bays. This is a condition that CEC staff have also seen while observing peak hour traffic operations.

Accidents along the corridor are historically located at the Lake Hefner intersection due to driver-related occurrences. Between 2015 and 2021, there have been a total of 5 collisions along the project extents. While there have been some injuries, none of the recorded crashes have been fatal. According to the traffic study, the studied intersection is not considered a high-collision area.

Pedestrian Access and Bus Facilities

Presently, there is no existing sidewalk within the project limits. During our site visits, there was pedestrian traffic and evidence of paths where pedestrians had previously walked observed along the exit ramps from Lake Hefner Parkway. There are currently plans to install an ADA sidewalk corridor along the north side of Expressway under MS-0127. There are not any bike routes along this corridor. However, there is a bike route to the east along N Independence Ave. The proposed project will not interfere with the Independence bike route.

In terms of alternative transportation, the Bus Rapid Transit (BRT) is scheduled to be operatable in late 2023. The alignment is proposed to be along Independence Avenue and Hospital Road. This alignment is not in interference with proposed improvements in TC-0598.

Existing Utilities

The observed existing utilities along this corridor include electrical lines, light poles, water lines and gas lines.

- Gas lines – There is a large 20" transmission main behind the retaining wall above the Lake Hefner Parkway Northbound Exit ramp that crosses the highway on a utility bridge in line with Hospital Road. It will not conflict with the proposed project.
- Water lines – There is an existing 12" water line on the south side of NW expressway that continues down the west side of the hospital. It will not conflict with the proposed project.
- Sewer Lines- The only nearby sewer is above the northbound exit ramp along the west side of the hospital and will not conflict with the project.

- Light poles – Located throughout the project and several are anticipated to need relocation due to conflicts with widenings.
- ATT & Cox – These utilities do not have anything in the project vicinity and will not be impacted.

CEC will hold a utility conference during design to confirm the above and make sure that nothing is missing.

Light Poles

There are four existing roadway light poles located throughout the project that will conflict with proposed turn bay widenings as shown in Figure 5. This lighting system operates at 240 volts and is connected by an underground circuit to pole bases with 2/c4AL wire. Inside the poles there is a pair of #12 gage wires running up to the luminaire.

- NBR: It is expected that the southernmost light pole (Hefner Pkwy Sta. 631+60), at the tip of where the extended turn bay begins, can be removed and that a second luminaire can be affixed to the existing pole 170 feet to the north to provide coverage.
- NBR: The second pole to the north (Expressway Sta. 1290+50) will need to be removed with a new pole footing installed 15 feet to the SE at Expressway Sta. 1290+65.
- WBR: The first pole for the westbound right bay extension that will require relocation is located at Expressway Sta. 1296+20. The new pole will need to be pushed back to maintain a 4' minimum offset.
- WBR: The second pole for the westbound right bay extension that requires relocation is at Expressway Sta. 1293+95. This pole will also need to be moved back to maintain minimum offset.

It is expected that about 590 feet of new electrical conduit that services light poles will also have to be relocated as the existing conduit is inside of the proposed widening footprint. This will require new wiring to be run through this section. After a roadway configuration has been agreed upon, CEC will calculate roadway lumens to ensure current or better performance Illuminating Engineering Society (IES) results.




Figure 5- Light Pole Relocations

Drainage

The NW Expressway and Lake Hefner Parkway intersection has a closed drainage system. Some inlets may need to be replaced or relocated as part of construction. Location and sizes of existing drainage structures can be seen in the preliminary plans provided in Appendix B. A preliminary drainage report noting specific drainage structures that need to be replaced has been provided to the city under a separate cover.

PROPOSED IMPROVEMENTS

To improve traffic operations for the intersection of the northbound Hefner Parkway ramps with NW Expressway, CEC proposes the following improvements:

- Expressway Westbound Right Turn Bay
 - Lengthen the westbound right turn bay to provide 800 total feet of storage length, primarily for the purpose of extending past westbound queues that regularly block access to the existing turn bay during heavy traffic.
- Lake Hefner Parkway Northbound Off Ramp
 - Lengthen the northbound right turn bay to provide 510 total feet of storage length, primarily for the purpose of extending past northbound queues that regularly block access to the existing turn bay during heavy traffic.

- Reconfigure northbound right turn bay by raising the profile to promote better sight distance and flattening the end portion of the ramp to improve the ability to accelerate onto Expressway.
- Adjust stop bar for northbound left turn bays and employ multiple methods to encourage vehicles to comply and stay out of sight lines for northbound right turn bay.
- Relocate the traffic signal serving eastbound traffic that obstructs the view.

Proposed improvements for the extended westbound right turn bay are straight forward in the sense that once access to this turn bay is improved, it will have plenty of capacity to serve demand. This is especially true considering that it gets overlapping right of way while EB and WB phases are running and is essentially under the same conditions to right-turn-on-red while northbound left movements are running given the very low volume of through moving traffic. According to turning movement counts collected by TEC this was only 23 vehicles northbound through vehicles over the course of a day out of 14,021 daily vehicles at this approach. This is roughly the same as saying there are less than 2 northbound through vehicles for every 1000 arriving at that approach.

The chief improvement to the northbound right turn movement will be the lengthening of its turn bay to 510 feet so that it is not as easily blocked by queuing northbound left vehicles. Improvements proposed for the northbound approach to NW Expressway are geared toward improving driver sight distance and ability to accelerate while still maintaining geometrics that allow a WB-67 vehicle to turn onto NW Expressway without turning through multiple lanes of traffic. As discussed previously, vehicles waiting for a gap to turn into on expressway are vertically set about 10 inches lower than traffic on the southernmost lane of NW Expressway. This will be improved by rebuilding the vertical profile of the northbound right turn bay and raising the position about 8 inches higher than it currently is at the end of the ramp. Part of the revised alignment is to shift the northbound right lane away from the through lanes at 26.66:1 to facilitate a vertical grade break between the lanes. This proposed improvement will also flatten out the area in which northbound right vehicles wait to turn right onto NW Expressway from what is currently a 2.6% upgrade to a 0.4% upgrade.

The west facing traffic signal can be relocated within the island by installing a new signal offset 5 feet further from expressway and 10 feet SE with at 55-foot mast arm. This will allow most of the work to be performed without having to impact signal operation and minimize down time. Wiring will fortunately be straightforward as this is the same corner as the traffic controller. Additionally, while it is a minor adjustment, CEC also proposes to push back the northbound stop bar back one foot to encourage vehicles to stay out sight lines for the yielding northbound right movement and employ other tactics to encourage compliance.




Figure 6- Northbound Right Sight Line

Taken altogether, this will improve access to the northbound right during heavy traffic and improve safety and capacity by alleviating factors that limit sight distance and provide a space that is easier for vehicles to accelerate out of. Essentially, the sight distance and grade improvements will lower the threshold for gap acceptance (or perceiving enough space between cars) and allow more drivers to safely enter the roadway while operating under yield control.

OTHER CONCEPTS

CEC has investigated other ideas aimed at improving traffic operations for this intersection, but for various reasons are not recommended:

Concept 1: Create an Auxiliary Lane on NW Expressway to receive northbound right turning vehicles.

Concept 2: Dual Northbound Right Lanes from exit ramp, signal controlled.

Concept 3: Create a raised concrete island ("porkchop") for northbound on-ramp.

Concept 4: Modified angle of entry for northbound right turn

Concept 1

This concept sought to eliminate yield control for the northbound right movement out of the exit ramp from Lake Hefner Parkway by providing a protected lane to enter onto. The goal of this would be to increase capacity for that movement and improve safety.



Figure 7- Concept 1 Auxiliary Lane

If this lane were to be implemented, its length up to the current hospital entrance would be approximately 340 feet. This length is below the minimum deceleration lane length of 350 feet according to section 10 of the AASHTO manual. CEC has considered multiple potential solutions to get above this minimum distance. One solution would be to move the hospital entrance farther down Northwest Expressway to the southeast. This is considered a non-starter as this is also the primary entrance to Integris Baptist for emergency vehicles. Furthermore, this would require the westbound left turn bay into this drive to be similarly shifted to the southeast and thereby interfere with the eastbound left turn bay at the intersection of Expressway and Independence. There are also special considerations that must be taken for this location. Emergency vehicles will likely be traveling urgently at speeds higher than the posted limit, meaning that the minimum deceleration lane length would need to be even longer than 350 feet to be compliant with AASHTO standards. Using a lane length of less than 350 feet would create unsafe weaving movements and driver awareness problems between vehicles exiting Lake Hefner Parkway and emergency vehicles turning into the hospital. This cannot be fixed without widening the bridge over Hefner Parkway to add an additional lane to the west. For these safety reasons the concept was abandoned.

Concept 2

This second concept was to add a second northbound right turn bay to the exit ramp past the north end of the existing retaining walls. Adding a second turn northbound right turn bay would necessitate the need for a stop bar and control from additional signal heads. This is because adding a second lane without stop control could create a confusing condition where the inside lane has a protected lane while the outer turn lane is yield controlled. Currently, the single yield control lane effectively gets the right of way while the northbound left movement has the green light.

Concept 3

CEC evaluated the possibility of adding a porkchop to the northbound on-ramp to direct northbound through moving vehicles to the left lane and delineate the eastern northbound lane to be exclusively for westbound right turning vehicles in what would be a relatively low-cost solution. See Figure 8 below.



Figure 8- Raised Concrete Island

According to turning movement counts there are approximately 23 northbound through vehicles at this intersection. This concept, at least as shown in Figure 8 is not feasible due to the need to accommodate dual eastbound left turning lanes.

Alternatively, CEC has investigated widening the northbound on-ramp to accommodate a third lane dedicated to the westbound right movement. Constructing such an improvement would require the relocation of two additional light poles and over 250 feet of 9-inch P.C. concrete auxiliary lane. This may not be worthwhile considering the additional cost. The low volume of northbound-through moving vehicles that westbound right vehicles are already required to yield to other traffic when they have the red light. This has been included as Alternate 1 and an exhibit is included in Appendix C.

Concept 4

The fourth concept is to change the angle at which the off-ramp from Lake Hefner Parkway meets NW Expressway. Currently, motorists have to look back over their shoulder in order to check for traffic which can be challenging. According to section 9 of the AASHTO manual, an angle of 112 degrees is ideal for a yield-controlled entry to a cross street where higher turning speeds are encouraged and pedestrian use is limited. However, causing vehicles to merge at a sharper angle would mean that WB-67 vehicles would be forced to cross over one lane of traffic to merge into the middle lane. This would limit semis' abilities to find appropriate gaps in traffic as well as slow down cars behind them. Because of this, concept 4 was not pursued.

DRAINAGE

The existing drainage along project TC-0598 contains closed drainage systems for runoff from the northbound on-ramp, northbound off-ramp, and NW Expressway. These systems consist of curb inlets and concrete pipes, and the zoning categories included in this project are Community Commercial (C3) and General Office (C2). According to the Oklahoma City Drainage Ordinance, several inlets were found to be out of compliance. Ex-1, Ex-2, Ex-3, and Ex-4 are out of compliance due to flow exceeding existing capacity. Ex-1, Ex-5, and Ex-6 are out of compliance due to exceeding the allowable spread.

Table 1: Proposed Structure Improvements			
EXISTING STR NO.	EXISTING STUCTURE SIZE	PROPOSED STR. NO.	PROPOSED STUCTURE SIZE
<i>EX-1</i>	<i>Design 2-2</i>	1	Design 7
<i>EX-2</i>	<i>Design 2-1</i>	2	Design 3-2
<i>EX-3</i>	<i>Design 1-0</i>	3	Design 2-1
<i>EX-4</i>	<i>Design 2-0</i>	4	Design 2-1
<i>EX-6</i>	<i>Design 3-0</i>	5	Design 3-0
<i>EX-7</i>	<i>Design 3-2</i>	6	Design 3-2
Note: Inlets being replaced with like-kind are those that meet capacity requirements and only need to be relocated			

PRELIMINARY COST ESTIMATES

Table 2: Preliminary Project Descriptions and Estimates	
Base Bid – TC-0598 / JP #35921(04) <ul style="list-style-type: none"> • Extend WB right turn bay to 800 LF of storage • Extend NB right turn bay to 510 LF of storage • Reconstruct NB off ramp for improved geometrics • Relocate signal pole to improve sight distance 	\$1,144,927
Alternate 1 <ul style="list-style-type: none"> • Dedicated lane on NB off ramp for WB right turns • Removes conflicts with NB vehicles 	\$279,409
CITY OF OKLAHOMA CITY BUDGET	\$2,108,204

Total Fixed Limit of Construction Budgeted for TC-0598	\$2,108,204
Total Proposed Construction Cost for TC-0598	<u>\$1,144,927</u>
Total Under Construction Budget:	\$963,277

These costs are based on the most recent bid tabs available. Detailed preliminary cost estimates can be found in Appendix A.

RECOMMENDATIONS

The purpose of this study is to implement recommendations of the TC-0598 traffic study and investigate solutions to address the identified traffic operations issues for the intersection of Hefner Parkway with NW Expressway. CEC makes the following recommendations:

- Lengthen the existing westbound right turn bay on NW Expressway to provide 800 total feet of storage.
- Reconstruct the northbound right turn bay on the Hefner Parkway exit ramp and lengthen to provide a total of 510 linear feet of storage length.
 - Revised geometrics will improve sight distance and aid acceleration onto NW Expressway. The northbound left stop bar will also be shifted back and the existing signal pole servicing eastbound traffic will be relocated.
- Replace and upsize four storm sewer inlets.

These improvements will improve the overall operation of the project intersection by increasing capacity for the right turn movements that will now be able to access the turn bays even when there are long queues for the primary movement. Additionally, improved geometrics will also make the northbound right turn easier to navigate for motorists with improved visibility and ease of entering the roadway.

The total cost for these improvements is estimated at \$1,144,927 which is \$963,277 under the overall fixed limit of construction budgeted for this project. Total cost breakdown can be found in Appendix A.

APPENDIX A

PRELIMINARY COST ESTIMATES



30% Construction Estimate

October 31, 2023



TC-0598 NW EXPRESSWAY AND LAKE HEFNER PARKWAY

SECTION	ITEM	ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
201(A)	1200	1	CLEARING AND GRUBBING	LSUM	1.0	\$ 5,000.00	\$ 5,000.00
202(A)	2200	2	UNCLASSIFIED EXCAVATION	C.Y.	625.0	\$ 10.00	\$ 6,250.00
221(B)	2300	3	TEMPORARY SILT FENCE	L.F.	1,600.0	\$ 3.00	\$ 4,800.00
221(C)	2400	4	TEMPORARY SEDIMENT FILTER	EA.	7.0	\$ 300.00	\$ 2,100.00
230(A)	7200	5	SOLID SLAB SODDING	S.Y.	1,444.0	\$ 3.00	\$ 4,332.00
303(A)	1200	6	AGGREGATE BASE TYPE A	C.Y.	386.0	\$ 90.00	\$ 34,740.00
407(B)	7300	7	TACK COAT	GAL	120.0	\$ 5.00	\$ 600.00
411(B)	1330	8	SUPERPAVE, TYPE S3 (PG 58-28 OK)	TON	1,449.0	\$ 130.00	\$ 188,370.00
411(D)	1520	9	SUPERPAVE, TYPE S5 (PG 70-28 OK)	TON	1,250.0	\$ 135.00	\$ 168,750.00
412	3100	10	COLD MILLING PAVEMENT	S.Y.	10,476.0	\$ 4.00	\$ 41,904.00
414(G)	5800	11	P.C. CONCRETE FOR PAVEMENT	C.Y.	260.0	\$ 250.00	\$ 65,000.00
600(B)	300	12	(PL) AUDIO/VIDEO CONSTRUCTION RECORDING	LSUM	1	\$ 6,000.00	\$ 6,000.00
609(B)	4375	13	2'-8" COMB.CRB. & GUT.(8" BARRIER)	L.F.	1,548.0	\$ 50.00	\$ 77,400.00
610(B)	5320	14	8" CONCRETE DRIVEWAY	S.Y.	320.0	\$ 140.00	\$ 44,800.00
611(G)	7758	15	INLET CI DES. 2 (B)	EA.	2.0	\$ 8,000.00	\$ 16,000.00
611(G)	7786	16	INLET CI DES. 3 (STD)	EA.	1.0	\$ 10,000.00	\$ 10,000.00
611(G)	7794	17	INLET CI DES. 3 (D)	EA.	2.0	\$ 11,000.00	\$ 22,000.00
611(G)		18	INLET CI DES. 7	EA.	1.0	\$ 16,000.00	\$ 16,000.00
612(A)	3200	19	MANHOLE ADJUST TO GRADE	EA.	2.0	\$ 1,700.00	\$ 3,400.00
612(E)	3600	20	PULL BOXES ADJUST TO GRADE	EA.	1.0	\$ 500.00	\$ 500.00
613(A)	5208	21	18" R.C. PIPE CLASS III	L.F.	122.0	\$ 106.00	\$ 12,932.00
619(B)	6356	22	REMOVAL OF CURB AND GUTTER	L.F.	1,449.0	\$ 11.00	\$ 15,939.00
619(B)	6360	23	REMOVAL OF CONCRETE PAVEMENT	S.Y.	746.0	\$ 10.00	\$ 7,460.00
619(B)	6364	24	REMOVAL OF ASPHALT PAVEMENT	S.Y.	655.0	\$ 7.00	\$ 4,585.00
619(B)	6368	25	REMOVAL OF DRAINAGE INLETS	EA.	6.0	\$ 710.00	\$ 4,260.00
619(B)	6380	26	REMOVAL OF CONCRETE DRIVEWAY	S.Y.	320.0	\$ 18.00	\$ 5,760.00

ROADWAY TOTAL: \$768,882.00

SECTION	ITEM	ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
802		27	LIGHT POLE WIRING	LSUM	1.0	\$ 50,000.00	\$ 50,000.00
802(B)	0324	28	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	L.F.	583.0	\$ 30.00	\$ 17,490.00
803(A)	1210	29	PULL BOX (SIZE I)	EA.	5.0	\$ 2,000.00	\$ 10,000.00
804(A)	2200	30	STRUCTURAL CONCRETE	C.Y.	7.0	\$ 1,400.00	\$ 9,800.00
804(B)	2300	31	REINFORCING STEEL	LB	1,023.8	\$ 4.00	\$ 4,095.20
805		32	LIGHT POLE FOOTING	EA.	4.0	\$ 8,000.00	\$ 32,000.00
805(D)	3504	33	REMOVE AND RESET LIGHT POLE	EA.	4.0	\$ 6,000.00	\$ 24,000.00
806(A)	4264	34	32'MH POLE,55'TS & 10'LMA(G.STL.)	EA.	1.0	\$ 80,000.00	\$ 80,000.00
834(A)	6235	35	2/C TRAFFIC SIGNAL ELECTRICAL CABLE	L.F.	60.0	\$ 10.00	\$ 600.00
834(A)	6235	36	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	L.F.	120.0	\$ 15.00	\$ 1,800.00
834(A)	6205	37	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	L.F.	30.0	\$ 25.00	\$ 750.00
856(A)	8200	38	TRAFFIC STRIPE (MULTI-POLY)(4" WIDE)	L.F.	1,715.0	\$ 1.00	\$ 1,715.00
856(A)	8208	39	TRAFFIC STRIPE (MULTI-POLY)(6" WIDE)	L.F.	2,730.0	\$ 1.25	\$ 3,412.50
856(A)	8208	40	TRAFFIC STRIPE (MULTI-POLY)(8" WIDE)	L.F.	748.0	\$ 2.00	\$ 1,496.00
856(A)	8216	41	TRAFFIC STRIPE (MULTI-POLY)(24" WIDE)	L.F.	53.0	\$ 12.00	\$ 636.00
856(B)	8304	42	TRAFFIC STRIPE (MULTI-POLY)(ARROWS)	EA.	13.0	\$ 250.00	\$ 3,250.00
						TRAFFIC TOTAL:	\$241,044.70

SECTION	ITEM	ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
880(J)	7110	43	CONSTRUCTION TRAFFIC CONTROL	LSUM	1.0	\$ 60,000.00	\$ 60,000.00

TRAFFIC TOTAL:							\$60,000.00
----------------	--	--	--	--	--	--	-------------


SECTION	ITEM	ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
642(B)	3300	44	CONSTRUCTION STAKING LEVEL II	LSUM	1.0	\$ 20,000.00	\$ 20,000.00
TOTAL:							\$20,000.00

SECTION	ITEM	ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
220	1100	45	SWPPP DOCUMENTATION AND MANAGEMENT	LSUM	1.0	\$ 5,000.00	\$ 5,000.00
641	2100	46	MOBILIZATION	LSUM	1.0	\$ 50,000.00	\$ 50,000.00
TOTAL:							\$55,000.00

TOTAL: \$1,144,927


APPENDIX B

PRELIMINARY CONSTRUCTION PLANS




TYPICAL SECTION NO. 1

EXIT RAMP WIDENING
 STATION: 631+26 TO 635+47.77



TYPICAL SECTION NO. 2

EXIT RAMP
 STATION: 100+00 TO 101+91



TYPICAL SECTION NO. 3

NW EXPRESSWAY WIDENING
 STATION: 1281+60 TO 1284+35

ROADWAY PAY QUANTITIES			
ITEM	ITEM NO.	DESCRIPTION	UNIT
201(A)	1	CLEARING AND GRUBBING	LSUM
202(A)	2	UNCLASSIFIED EXCAVATION	C.Y.
202(H)	3	TEMPORARY CONCRETE WASHOUT	LSUM
221(B)	4	TEMPORARY SILT FENCE	(R-8)(10) L.F.
221(C)	5	TEMPORARY SEDIMENT FILTER	(R-8)(10) EA.
230(A)	6	SOLID SLAB SODDING	(R-6)(R-7) S.Y.
308(A)	7	AGGREGATE BASE TYPE A	(6) C.Y.
407(B)	8	TACK COAT	(R-25) GAL.
411(B)	9	SUPERPAVE. TYPE S3 (PG 58-28 OK)	(R-26) TON
411(D)	10	SUPERPAVE. TYPE S5 (PG 70-28 OK)	(R-26) TON
412	11	COLD MILLING PAVEMENT	(R-29)(7) S.Y.
414(G)	12	P.C. CONCRETE FOR PAVEMENT	(9) LSUM
600(B)	13	(P-L) AUDIO/VIDEO CONSTRUCTION RECORDING	C.Y.
608(B)	14	2'-8" COMB.CRB. & GUT.(8" BARRIER)	(9) L.F.
610(B)	15	8" CONCRETE DRIVEWAY	S.Y.
611(G)	16	INLET CI DES. 2 (8)	(R-34)(R-35) EA.
611(G)	17	INLET CI DES. 3 (STD)	(R-34)(R-35) EA.
611(G)	18	INLET CI DES. 3 (D)	(R-34)(R-35) EA.
611(G)	19	INLET CI DES. 7	EA.
612(A)	20	MANHOLE ADJUST TO GRADE	(8) EA.
612(E)	21	PULL BOXES ADJUST TO GRADE	(8) EA.
613(A)	22	18" R.C. PIPE CLASS III	(3) L.F.
619(B)	23	REMOVAL OF CURB AND GUTTER	(R-40) L.F.
619(B)	24	REMOVAL OF CONCRETE PAVEMENT	(R-40)(R-41) S.Y.
619(B)	25	REMOVAL OF ASPHALT PAVEMENT	(R-40)(R-41) S.Y.
619(B)	26	REMOVAL OF DRAINAGE INLETS	(R-40) EA.
619(B)	27	REMOVAL OF CONCRETE DRIVEWAY	(R-40)(R-41) S.Y.

TRAFFIC PAY QUANTITIES			
ITEM	ITEM NO.	DESCRIPTION	UNIT
802	27	LIGHT POLE WIRING	LSUM
802(B)	28	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	L.F.
803(A)	29	PULL BOX (SIZE I)	EA.
804(A)	30	STRUCTURAL CONCRETE	C.Y.
804(B)	31	REINFORCING STEEL	LB
805	32	LIGHT POLE FOOTING	EA.
805(D)	33	REMOVE AND RESET LIGHT POLE	EA.
806(A)	34	32" MH POLE SST'S & JOINTS (6 STL.)	EA.
806(A)	35	2" C TRAFFIC SIGNAL ELECTRICAL CABLE	L.F.
804(A)	36	2 1/2" C TRAFFIC SIGNAL ELECTRICAL CABLE	L.F.
806(A)	37	2 1/2" C TRAFFIC SIGNAL ELECTRICAL CABLE	L.F.
806(A)	38	TRAFFIC STRIPE (MULTI-POLY)(4" WIDE)	L.F.
806(A)	39	TRAFFIC STRIPE (MULTI-POLY)(8" WIDE)	L.F.
806(A)	40	TRAFFIC STRIPE (MULTI-POLY)(16" WIDE)	L.F.
806(A)	41	TRAFFIC STRIPE (MULTI-POLY)(24" WIDE)	L.F.

TRAFFIC PAY QUANTITIES			
ITEM	ITEM NO.	DESCRIPTION	UNIT
0303 - TEMPORARY			

PAY QUANTITIES			
ITEM	ITEM NO.	DESCRIPTION	UNIT
0600 - STAKING			

PAY QUANTITIES			
ITEM	ITEM NO.	DESCRIPTION	UNIT
0640 - CONSTRUCTION			
220	45	SWPPP DOCUMENTATION AND MANAGEMENT	LSUM

STORM WATER MANAGEMENT PLAN

CED-17-TRANSORATION
PRELIMINARY
PLANS
10/30/2023

SITE DESCRIPTION

PROJECT LIMITS: NW EXPRESSWAY FROM LAKE HEPNER PARKWAY TO INDEPENDENCE AVENUE

PROJECT DESCRIPTION: GRADE, DRAIN, AND SURFACE, NW EXPRESSWAY AND LAKE HEPNER PARKWAY, OKLAHOMA CITY, OKLAHOMA

SUGGESTED SEQUENCE OF EROSION CONTROL ACTIVITIES:

1. VEGETATIVE STRIPPING
2. UNDERCUT & STOCKPILE EXISTING TOPSOIL
3. INSTALL PERIMETER EROSION CONTROL MEASURES
4. SIDEWALK EXCAVATION AND EMBANKMENT
5. CONST. NEW STORM INLETS
6. INSTALL TEMP. SEDIMENT FILTERS
7. CONST. FINISHED SIDEWALK PAVING AND ROADWAY SURFACING
8. SPREAD TOPSOIL
9. INSTALL SOLID SLAB SOG

SOIL TYPE: TELLERBURN LAND COMPLEX

TOTAL AREA OF THE CONSTRUCTION SITE: 2.8 AC.

ESTIMATED AREA TO BE DISTURBED: 9.81 AC.

OFFSITE AREA TO BE DISTURBED: (FOR CONTRACTOR USE) NA

TOTAL IMPERVIOUS AREA PRE-CONSTRUCTION: 2.37 AC.

TOTAL IMPERVIOUS AREA POST-CONSTRUCTION: 2.55 AC.

POST-CONSTRUCTION RUNOFF COEFFICIENT OF THE SITE: 0.67

LATITUDE & LONGITUDE OF CENTER OF PROJECT: 35°13'32.87" N, 97°24'39.93" W

PROJECT WILL DISCHARGE TO: CLOVERLEAF CREEK

NAME OF RECEIVING WATERS: CLOVERLEAF CREEK

SENSITIVE WATERS OR WATERSHEDS: YES ☐ NO ☒

303(d) IMPAIRED WATERS: YES ☐ NO ☒

IF YES, LIST IMPAIRMENT: YES ☒ NO ☐

LOCATED IN A TMDL: YES ☒ NO ☐

LAKE THUNDERBIRD TMDL: YES ☒ NO ☐

MS4 ENTITY: YES ☒ NO ☐

IF YES, LOCATION: OKLAHOMA CITY

NOTE:
THIS SHEET SHOULD BE USED IN CONJUNCTION WITH A DRAINAGE MAP THAT ILLUSTRATES THE DRAINAGE PATTERNS, PATHWAYS AND RECEIVING WATERS FOR THIS PROJECT. THIS SHEET SHOULD ALSO BE USED WITH THE EROSION CONTROL SUMMARIES, PAY ITEMS, & NOTES.

EROSION AND SEDIMENT CONTROLS

SOIL STABILIZATION PRACTICES:

- PERMANENT SEEDING ☒
- PERMANENT SODDING, SPRIGGING OR SEEDING ☒
- VEGETATIVE MULCHING ☒
- SOIL RETENTION BLANKET ☒
- PRESERVATION OF EXISTING VEGETATION ☒

NOTE: TEMPORARY EROSION CONTROL METHODS MUST BE USED ON ALL DISTURBED AREAS WHERE CONSTRUCTION ACTIVITIES HAVE CEASED FOR OVER 14 DAYS. METHODS USED WILL BE AS SHOWN ON PLANS, OR AS DIRECTED BY THE ENGINEER.

STRUCTURAL PRACTICES:

- STABILIZED CONSTRUCTION EXIT ☒
- TEMPORARY SILT FENCE ☒
- TEMPORARY SILT DIKES ☒
- TEMPORARY FIBER LOG ☒
- DIVERSION, INTERCEPTOR OR PERIMETER DIKES ☒
- DIVERSION, INTERCEPTOR OR PERIMETER SWALES ☒
- ROCK FILTER DAMS ☒
- TEMPORARY SLOPE DRAIN ☒
- PAVED DITCH W/ DITCH LINER PROTECTION ☒
- TEMPORARY DIVERSION CHANNELS ☒
- TEMPORARY SEDIMENT BASINS ☒
- TEMPORARY SEDIMENT TRAPS ☒
- TEMPORARY SEDIMENT FILTERS ☒
- TEMPORARY SEDIMENT REMOVAL ☒
- RIP RAP ☒
- INLET SEDIMENT FILTER ☒
- TEMPORARY BRUSH SEDIMENT BARRIERS ☒
- SANDBAG BERMES ☒
- TEMPORARY STREAM CROSSINGS ☒

OFFSITE VEHICLE TRACKING:

- HAUL ROADS DAMPENED FOR DUST CONTROL ☒
- LOADED HAUL TRUCKS TO BE COVERED WITH TARP/AULIN ☒
- EXCESS DIRT ON ROAD REMOVED DAILY ☒

NOTES:

THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR THE FOLLOWING:

MAINTENANCE AND INSPECTION:
ALL EROSION AND SEDIMENT CONTROLS WILL BE MAINTAINED IN GOOD WORKING ORDER FROM THE BEGINNING OF CONSTRUCTION UNTIL AN ACCEPTABLE VEGETATIVE COVER IS ESTABLISHED. INSPECTION BY THE CONTRACTOR AND ANY NECESSARY REPAIRS SHALL BE PERFORMED ONCE EVERY 7 CALENDAR DAYS AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCH AS RECORDED BY A NON-FREEZING RAIN GAUGE TO BE LOCATED ON SITE. POTENTIALLY ERODIBLE AREAS, SLOPES, EXITS, LONG WITH EROSION AND SEDIMENT CONTROL LOCATIONS ARE EXAMPLES OF SITES THAT NEED TO BE INSPECTED.

WASTE MATERIALS:
PROPER MANAGEMENT AND DISPOSAL OF CONSTRUCTION WASTE MATERIAL IS REQUIRED BY THE CONTRACTOR. MATERIALS INCLUDE STOCKPILES, SURPLUS, DEBRIS AND ALL OTHER BY-PRODUCTS FROM THE CONSTRUCTION PROCESS. PRACTICES INCLUDE DISPOSAL, SPILL PREVENTION AND CLEANUP MEASURES. CONTROLS AND PRACTICES SHALL MEET THE REQUIREMENTS OF ALL FEDERAL, STATE AND LOCAL AGENCIES.

HAZARDOUS MATERIALS:
PROPER MANAGEMENT AND DISPOSAL OF HAZARDOUS WASTE MATERIALS IS REQUIRED. THE CONTRACTOR IS RESPONSIBLE FOR FOLLOWING MANUFACTURER'S RECOMMENDATIONS, STATE AND FEDERAL REGULATIONS TO ENSURE CORRECT HANDLING, DISPOSAL, SPILL PREVENTION AND CLEANUP MEASURES. EXAMPLES INCLUDE BUT ARE NOT LIMITED TO: PAINTS, ACIDS, CLEANING SOLVENTS, CHEMICAL ADDITIVES, CONCRETE CURING COMPOUNDS AND CONTAMINATED SOILS.


GENERAL NOTES:
A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS REQUIRED TO COMPLY WITH THE NATIONAL POLLUTION DISCHARGE ELIMINATION ACT (NPDES) PRE-CONSTRUCTION REQUIREMENTS. THIS PLAN IS INITIATED DURING THE DESIGN PHASE, CONFIRMED IN THE PRE-WORK MEETINGS AND AVAILABLE ON THE JOB SITE ALONG WITH COPIES OF THE NOTICE OF INTENT (NOI) FORM AND PERMIT CERTIFICATE THAT HAVE BEEN FILED WITH THE OKLAHOMA DEPARTMENT OF ENVIRONMENTAL QUALITY (ODEQ). THE PLAN MUST BE KEPT CURRENT WITH UP-TO-DATE AMENDMENTS DURING THE PROJECT. SWPPP MUST BE SUBMITTED IN THE SWPPP (I.E. BEFORE ANY WORK BEGINS) WITH SITES, ASPHALT/CONCRETE PLANTS ETC. THE BASIC GOAL OF STORM WATER MANAGEMENT IS TO IMPROVE WATER QUALITY BY REDUCING POLLUTANTS IN STORM WATER DISCHARGES. RUNOFF FROM CONSTRUCTION SITES HAS A POTENTIAL FOR POLLUTION DUE TO EXPOSED SOILS AND THE PRESENCE OF HAZARDOUS MATERIALS USED IN THE CONSTRUCTION PROCESS. THE PRESENCE OF HAZARDOUS MATERIALS ON THE CONSTRUCTION SITE MAY REQUIRE THE INTERVENTION OF THESE REGULATIONS BEFORE LEAVING THE CONSTRUCTION SITE ARE THE BEST PRACTICES FOR CONTROLLING STORM WATER POLLUTION.

THE FOLLOWING SECTIONS OF THE 2019 ODOT STANDARD SPECIFICATIONS SHOULD BE NOTED:


- 103.05 BONDING REQUIREMENTS
- 104.10 FINAL CLEANING UP
- 104.12 CONTRACTOR'S RESPONSIBILITY FOR WORK
- 104.13 ENVIRONMENTAL PROTECTION
- 106.08 STORAGE AND HANDLING OF MATERIAL
- 107.01 LAWS, RULES AND REGULATIONS TO BE OBSERVED
- 107.20 STORM WATER MANAGEMENT
- 220 MANAGEMENT OF EROSION, SEDIMENTATION AND STORM WATER POLLUTION PREVENTION AND CONTROL
- 221 TEMPORARY SEDIMENT CONTROL

IN ADDITION:
"ODEQ GENERAL PERMIT (OKR10) FOR STORM WATER DISCHARGES FROM CONSTRUCTION ACTIVITIES WITHIN THE STATE OF OKLAHOMA" ODEQ, WATER QUALITY DIVISION, SEPTEMBER 13, 2017.

OKLAHOMA COUNTY
LAKE HEPNER PARKWAY
STORM WATER
MANAGEMENT PLAN
JOB FILE NO. 3502104
SHEET NO. 5001



NOTE: ALL DISTANCES SHOWN TO RIGHT-OF-WAY, FENCES, UTILITIES, AND OTHER EXIST. OBJECTS ARE FROM 1 OF SURVEY.



SCALE 1"=40'

0 40' 80'

OKLAHOMA COUNTY


TC-6588 NW EXPRESSWAY AND LAKE HEPNER PARKWAY

DRAINAGE MAP

JOB PIECE NO. 55521(D4) SHEET NO. 5001

CEC II TRANSPORTATION
 PRELIMINARY
 PLANS
 10/30/2023


NOTE: ALL DISTANCES SHOWN TO RIGHT-OF-WAY,
 FENCES, UTILITIES AND OTHER EXIST. OBJECTS ARE
 FROM TOP SURVEY.



SCALE 1"=30'
 0 20 40

LEGEND

ASPHALT	PAVEMENT
OVERLAY	CONCRETE




UTILITY OWNER CONTACT INFORMATION

OWNER	CONTACT	PHONE
AT&T	JIMMY FRANKLIN	405-246-2590
CITY OF OKC	SCOTT COX	405-267-2590
COX COMMUNICATIONS	MARK BOVLING	405-500-4296
OKC OKC METRO	RAE ANN LAWRENCE	405-503-5785
OKC	MARK BRUMLEY	918-431-4272

TC-6588 NW EXPRESSWAY AND
 LAKE HEVIER PARKWAY
 OKLAHOMA COUNTY
 PLAN & PROFILE
 SHEET 1 OF 5
 JOB PIECE NO. 25621604 SHEET NO. 1000L

CEC TRANSPORTATION
PRELIMINARY PLANS
 10/30/2023

NOTE: ALL DISTANCES SHOWN TO RIGHT-OF-WAY, FENCES, UTILITIES, AND OTHER EXIST. OBJECTS ARE FROM C.O.P. SURVEY.




LEGEND


ASPHALT	PAVEMENT
MILLS	OVERLAY
CONCRETE	PAVEMENT
	PAVEMENT



SCALE 1"=40'



OKLAHOMA COUNTY
 TC-0088 NW EXPRESSWAY AND LAKE HENNER PARKWAY
PLAN & PROFILE
 SHEET 2 OF 5
 JOB PIECE NO. 2552100
 SHEET NO. B003




NOTE: ALL DISTANCES SHOWN TO RIGHT-OF-WAY, FENCES, UTILITIES, AND OTHER EXIST. OBJECTS ARE FROM 1 OF SURVEY.




SCALE 1"=20'

LEGEND

ASPHALT	PAVEMENT
MILL & OVERLAY	CONCRETE




CEC // TRANSPORTATION
PRELIMINARY
PLANS
10/30/2023




CDC TRANSPORTATION
**PRELIMINARY
 PLANS**
 10/30/2023

NOTE: ALL DISTANCES SHOWN TO RIGHT-OF-WAY,
 FENCES, UTILITIES AND OTHER EXIST. OBJECTS ARE
 FROM 1" OF SURVEY.



SCALE 1"=20'
 0 20 40
 1"=20'

LEGEND
 ASPHALT
 MILL & PATCH
 OVERLAY
 CONCRETE



OKLAHOMA COUNTY
 TC-688 NW EXPRESSWAY AND
 LAKE HEFNER PARKWAY
PLAN & PROFILE
SHEET 5 OF 5
 JOB PIECE NO. 35521001 SHEET NO. 8006

APPENDIX C

ALTERNATE 1 EXHIBIT & ESTIMATE



30% Construction Estimate
October 31, 2023



**TC-0598 NW EXPRESSWAY AND LAKE HEFNER PARKWAY
ALTERNATE 1**

SECTION	ITEM	ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
201(A)	1200	1	CLEARING AND GRUBBING	LSUM	1.0	\$ 2,000.00	\$ 2,000.00
202(A)	2200	2	UNCLASSIFIED EXCAVATION	C.Y.	1,289.0	\$ 10.00	\$ 12,890.00
221(B)	2300	3	TEMPORARY SILT FENCE	L.F.	473.0	\$ 3.00	\$ 1,419.00
221(C)	2400	4	TEMPORARY SEDIMENT FILTER	EA.	1.0	\$ 300.00	\$ 300.00
230(A)	7200	5	SOLID SLAB SODDING	S.Y.	420.0	\$ 3.00	\$ 1,260.00
303(A)	1200	6	AGGREGATE BASE TYPE A	C.Y.	190.0	\$ 90.00	\$ 17,100.00
411(B)	1330	7	SUPERPAVE, TYPE S3 (PG 58-28 OK)	TON	143.0	\$ 130.00	\$ 18,590.00
414(G)	5800	8	P.C. CONCRETE FOR PAVEMENT	C.Y.	213.0	\$ 250.00	\$ 53,250.00
510(A)	1220	9	RETAINING WALL	LSUM	1.0	\$ 15,000.00	\$ 15,000.00
600(B)	300	10	(PL) AUDIO/VIDEO CONSTRUCTION RECORDING	LSUM	1.0	\$ 1,000.00	\$ 1,000.00
609(B)	4375	11	2'-8" COMB.CRB. & GUT.(8" BARRIER)	L.F.	645.0	\$ 35.00	\$ 22,575.00
610(B)	5320	12	8" CONCRETE DRIVEWAY	S.Y.	122.0	\$ 95.00	\$ 11,590.00
611(G)	7758	13	INLET CI DES. 2 (B)	EA.	1.0	\$ 8,000.00	\$ 8,000.00
612(A)	3200	14	MANHOLE ADJUST TO GRADE	EA.	2.0	\$ 1,700.00	\$ 3,400.00
612(E)	3600	15	PULL BOXES ADJUST TO GRADE	EA.	1.0	\$ 500.00	\$ 500.00
613(A)	5216	16	18" R.C. PIPE CLASS III	L.F.	30.0	\$ 100.00	\$ 3,000.00
619(B)	6356	17	REMOVAL OF CURB AND GUTTER	L.F.	562.0	\$ 11.00	\$ 6,182.00
619(B)	6360	18	REMOVAL OF CONCRETE PAVEMENT	S.Y.	178.0	\$ 10.00	\$ 1,780.00
619(B)	6368	19	REMOVAL OF DRAINAGE INLETS	EA.	1.0	\$ 710.00	\$ 710.00
ROADWAY TOTAL:							\$180,546.00

SECTION	ITEM	ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
802		20	ELECTRICAL WIRING	LSUM	1.0	\$ 20,000.00	\$ 20,000.00
802(B)	0324	21	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	L.F.	426.0	\$ 30.00	\$ 12,780.00
803(A)	1210	22	PULL BOX (SIZE I)	EA.	5.0	\$ 2,000.00	\$ 10,000.00
805		23	LIGHT POLE FOOTING	EA.	3.0	\$ 8,000.00	\$ 24,000.00
805(D)	3504	24	REMOVE AND RESET LIGHT POLE	EA.	3.0	\$ 6,000.00	\$ 18,000.00
856(A)	8200	25	TRAFFIC STRIPE (MULTI-POLY)(4" WIDE)	L.F.	808.0	\$ 1.00	\$ 808.00
856(A)	8208	26	TRAFFIC STRIPE (MULTI-POLY)(6" WIDE)	L.F.	220.0	\$ 1.25	\$ 275.00
TRAFFIC TOTAL:							\$85,863.00


SECTION	ITEM	ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
880(J)	7110	27	CONSTRUCTION TRAFFIC CONTROL	LSUM	1.0	\$ 5,000.00	\$ 5,000.00
TRAFFIC TOTAL:							\$5,000.00

SECTION	ITEM	ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
642(B)	3300	28	CONSTRUCTION STAKING LEVEL II	LSUM	1.0	\$ 2,000.00	\$ 2,000.00
TOTAL:							\$2,000.00

TOTAL: \$273,409

CEC // TRANSPORTATION
PRELIMINARY
PLANS
10/30/2023

NOTE: ALL DISTANCES SHOWN TO RIGHT-OF-WAY,
FENCES, UTILITIES, AND OTHER EXIST. OBJECTS ARE
FROM 1 OF SURVEY.



TC-0988 NW EXPRESSWAY AND
LAKE HEPNER PARKWAY
OKLAHOMA COUNTY
ALTERNATE 1 EXHIBIT: NB
RAMP WIDENING
JOB PRICE NO. 35971049 SHEET NO. 1021