

AMENDMENT NO. 2
TO THE
PLANS AND SPECIFICATIONS
FOR THE
**OCAT CEPA 2104 REHABILITATE C.E. PAGE APRON
CLARENCE E. PAGE AIRPORT
OKLAHOMA CITY, OKLAHOMA**

February 24, 2022

This change consists of:

Signature Page
Description/Justification Pages
Itemized Breakdown and Supporting Documentation Pages


TOTAL AMENDMENT NO. 2

Increase (+) \$7,018.00


APPROVED:

FOR THE
DEPARTMENT OF AIRPORTS


Director of Airports


Trust Secretary

ATTEST: (Seal)


Assistant Municipal Counselor
And Trust Attorney


APPROVED:

FOR THE
OKLAHOMA CITY AIRPORT TRUST


Trust Chairman



Rudy Construction Co.


Shane Allen
Vice President

AMENDMENT NO. 2
OCAT CEPA 2104 REHABILITATE C.E. PAGE APRON
CLARENCE E. PAGE AIRPORT
February 24, 2022

Description and Justification

BASE BID NO. 1

ITEM NO. 1 Add (+) \$380.00

Description

Increase in quantity for pay item 6 – Concrete Pavement Removal by 38.00 square yards at \$10.00/square yard resulting in a new pay item quantity of 69.00 square yards.

Justification

A storm sewer pipe blockage discovered at the end of the project revealed collapsed pipe. Removal of concrete pavement was needed to remove and replace the broken pipe segments.

ITEM NO. 2 Add (+) \$2,505.00

Description

Increase in quantity for pay item 11 – 6" Crushed Aggregate Base by 167.00 square yards at \$15.00/square yard resulting in a new pay item quantity of 4,971.74 square yards.

Justification

A storm sewer pipe blockage discovered at the end of the project revealed collapsed pipe. Aggregate base was used to backfill the excavated trench needed to remove and replace the broken pipe segments.

ITEM NO. 3 Add (+) \$1,900.00

Description

Increase in quantity for pay item 12 – 7.5" P.C. Concrete Surface Course by 25.00 square yards at \$76.00/square yards resulting in a new pay item quantity of 5,085.00 square yards.

Justification

A storm sewer pipe blockage discovered at the end of the project revealed collapsed pipe. Concrete pavement was removed and replaced to allow for the broken pipe segments to be removed and replaced.

Subtotal Amendment No. 2 (Base Bid No. 1) Add (+) \$4,785.00

BASE BID NO. 2**ITEM NO. 1**

Add (+) \$1,245.00

Description

Increase in quantity for pay item 19 – 6" Crushed Aggregate Base by 83.00 square yards at \$15.00/square yard resulting in a new pay item quantity of 2,223.24 square yards.

Justification

A storm sewer pipe blockage discovered at the end of the project revealed collapsed pipe. Aggregate base was used to backfill the excavated trench needed to remove and replace the broken pipe segments.

ITEM NO. 2

Add (+) \$988.00

Description

Increase in quantity for pay item 20 – 7.5" P.C. Concrete Surface Course by 13.00 square yards at \$76.00/square yards resulting in a new pay item quantity of 1,303.00 square yards.

Justification

A storm sewer pipe blockage discovered at the end of the project revealed collapsed pipe. Concrete pavement was removed and replaced to allow for the broken pipe segments to be removed and replaced.

Subtotal Amendment No. 2 (Base Bid No. 2) Add (+) \$2,223.00

Grand Total Amendment No. 2 Add (+) \$7,018.00

In consideration of this change, Rudy Construction Co. contract is altered as follows:

Original Contract Amount	\$793,200.00
Amendment No. 1	\$10,962.35
Amendment No. 2	\$7,018.00
Change Order No. 1	\$2,159.01
Change Order No. 2	\$0.00
Change Order No. 3	\$15,794.25
Change Order No. 4	\$6,650.00
<u>New Contract Amount</u>	<u>\$835,783.61</u>

Original Contract Duration	80 calendar days
Change Order 1	1 calendar days
Change Order 2	14 calendar days
Change Order 3	9 calendar days
Change Order 4	71 calendar days

<u>New Contract Duration</u>	<u>175 calendar days</u>
------------------------------	--------------------------

<u>Completion Date</u>	<u>March 14, 2022</u>
------------------------	-----------------------

END OF AMENDMENT NO. 2